

Energy Saving by Installation of Double Bundle-type Heat Pump

IndonesiaJCM Model Project

Date: 22nd February 2016

Venue: Bogor, Indonesia

Project Owner:
(Japan) Toyota Tsusho Corporation,
(Indonesia) PT.TTL Residences

■ Project Outline

- 1) Location LIPPO Cikarang, Bekasi West Java, INDONESIA
- 2) Type, Use Hotel, Service apartment
- 3) Land Area 8,284m²
- 4) Structure RC structure 13 Floors (Maximum height 54.4m)
- 5) Floor Area 13,358m² (Residential area : 10,700m²)
- 6) Schedule 1st June 2013 ~ 31st July 2014 (14 Months)


■ Mechanical and Electrical Facility Outline

- 1) Substation 3 ϕ 3W 20kV/400-230V 1,000kVA x 1
- 2) Generator 3 ϕ 4W 400-230V 630VA x1 (50% Back up)
- 3) Main Feeder CVT Pre-fabrication Branch cable
- 4) Lighting Public : LED Down light, Tube FL Lamp Corridor 150Lx, Office 500Lx
Residence : LED Ceiling Lamp with Variable lumen and color
- 5) Weak current TEL, LAN, Pubric Address, CCTV, Card Key security
- 6) Plumbing Direct supply with inverter pump Under ground tank 240m³
- 7) Hot water Kitchen, SPA : Central system from Boiler 230kW x 2sets with solar
Residences : Local system with 100 liter hot water tank, and heater
- 8) Filtering SPA : 22m³/h(2turn/h), Swimming Pool : 16m³/h (4turn/day)
- 9) Fire fighting Splinkler, Internal and External Hydrant system, fire extinguisher
- 10) AC system Air cooled Heat pump with Freon R-410
Pubric area : Multi system with ceiling cassette
Residence : Single wall mounted and small multi system

■ Project Organization

Project Manager	Site Manager	ME manager	ME Chief	Total Site staff
Kitayama	Butarbutar	TADA	Yanto	63 staffs


■ Schedule Construction : July 2013 – September 2014 (15 months)



■ External view



■ Layout





Entrance



Lobby view from Pool



Papaya and AXIA



View from Moon Lake



Lobby



Type B



Restaurant



Public bath

■ Project Outline

- 1) Location LIPPO Cikarang, Bekasi West Java, INDONESIA
- 2) Type, Use Hotel, Service apartment, Restaurant
- 3) Land Area 8,284m²
- 4) Structure RC structure 13 Floors (Maximum height 52.88m)
- 5) Floor Area 13,303m² (Residential area : 8,219m²)
- 6) Schedule 1st Oct 2014 ~ 31st March 2016 (18 Months)

■ Mechanical and Electrical Facility Outline

- 1) Substation 3 ϕ 3W 20kV/400-230V 1,000kVA x 1
- 2) Generator 3 ϕ 4W 400-230V 630VA x1 (Back-up : 70%)
- 3) Main Feeder CVT Pre-fabrication Branch cable
- 4) Lighting Public : LED Down light, Tube FL Lamp Corridor 150Lx, Office 500Lx
Residence : LED Ceiling Lamp with Variable lumen and color
- 5) Weak current TEL, LAN, Pubric Address, CCTV, Card Key security
- 6) Plumbing Direct supply with inverter pump Under ground tank 60m³
- 7) Hot water Kitchen, SPA : Central system : 37.8kW x 6 set
Double bundled Heat pump With 45m³ hot water tank
Residences : Local system with 100 liter hot water tank. and heater
Only 12-13F rooms are included in central system
- 8) Filtering SPA : Internal Bath 22m³/h(2turn/h)、Roten(External) : 16m³/h (2turn/h)
- 9) Fire fighting Splinkler, Internal and External Hydrant system, fire extinguisher
- 10) AC system Public : Double bundled (Water cooled) chiller 27.6kW x 6set
with Heat storage tank 240m³, Secondary FCU, AHU
Residences : Wall mounted single type R-410

■ Organization

Project Manager	Site Manager	ME manager	ME Chief	Total Japanese	Indonesian staff
Kitayama	Butarbutar	TADA	Yanto	4 staffs	61 staffs


■ Schedule 1st Oct 2014 ~ 31st March 2016 (18 Months)

Time	2014												2015												2016				
Item	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11	12	1	2	3	4	5	6	7	8	9	10	11
CHR PROJECT 13 Floor (48m)																													
家具工事 / Furniture work																													
仕上工事 / Finishing works																													
躯体工事 / Structure works																													
掘削工事 / Excavation works																													
杭工事 / Piling works																													
整地工事 / level the ground																													

■ External View (Completed Image)






■ Layout



Funded by JCM Model Project

	Standard system (tower1) Boiler + VRV system	Advanced System (Tower2) Heat pump + AHU	
CO2 emission	: 450 ton-CO2/ year	→ 380 ton-CO2/ year	= 170 ton-CO2/ year
Solar consumption	: 112 m3/ year	→ 0 m3/ year	= 112m3/ year
Running Cost	: 980,000,000 Rp / year	→ 280,000,000 Rp/ year	= 700,000,000 Rp / year
Initial Cost	: 8,300 juta Rp.	→ 8,900 juta Rp.	= 600 juta Rp. up (Expected 0.8 year pay back)


System schematic



Double Bundled Heat Pump system (Water cooled chiller)


Why Save Energy and reduce CO2

Tower 1 (Standard system)




For making 5 degree cooler water
Discharge the 5 degree heat to air

Boiler system



For making 35 degree hotter water
Burn the solar for heating and CO2 discharge

Tower 2 (Advanced system)



For making 5 degree cooler water
Shift heat to Freon Cycle

For making 35 degree hotter water
Get Heat from Freon Cycle

Without discharge the Heat and CO2


What is the advanced technology

1. Sensitive Freon control

Hot water side 35°C differential

Cool water side 5 °C differential

Balanced in the same cycle



2. Heat balance design

Cooling water for Air Conditioning cannot be made **without Hot water Consumption**

Heat balance in the building designed equally

【Invention the Combined system of the Air conditioning and hot water supply Suited for the Tropic Region 】

Theme/Plan

- ①Reduction of CO2 emission
- ②Reduction of Fossil Fuel Consumption
- ③Less and Easier work for Facility Staff
- ④Better Profitability Balance
- ⑤Make Superiority in the Market

Solution/Do

- ①High Efficiency with Double bundled system
- ②No consumption of solar for heat source
- ③Better Reliability and Automatic Operations
- ④Reduction of Initial and Running Cost
- ⑤Symbolized as the Friendship between Indonesia - Japan

Achievement/Check

- Authorized as the JCM Project
- Get the Subsidy by Government
- Reduction of running cost Rp.700 juta/year
- Reduction of CO2 emission 170C-ton/year
- Invent the New Parallel operated small units


Development/Action

- Find best balance between cool and heat during the monitoring term of CO2 reduction
- Analyze the profitability except subsidy
- Establish the fascinating scheme from Japan only based on the Advanced technology and Subsidy





JCM authorized

Double bundled Heat pump



Cost comparison tower 1 and 2



Status of this Project

- Mar 2015: Installed all equipment
- Jun 2015: approved JCM Methodology
- Sep 2015: Start PDDF to end of Mar 2016
- Apr 2016: start System operation
- “**Validation**” within one year after start operation(Mar 2017)
- “**Verification** “ After one more year(Mar2018)

Thank you